BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

Tender No: BBMP/EE/DD/TEN/06/12-13 Date: 11.02.2013 Item No:

SCHEDULE-B

NAME OF WORK:Providing Cement concrete to Cross at Backside of Shubhodya School in Ward No.13 (2nd Call)

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **Sri ASWATHNARAYAN**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed complete as per specifications.	Cum	35.10	120.00	Rupees One Hundred Twenty Only
2	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	288.00	150.00	Rupees One Hundred Fifty Only
3	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	115.88	3700.00	Rupees Three Thousand Seven Hundred Only
4	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc. complete as per specifications.	Cum	92.70	4500.00	Rupees Four Thousand Five Hundred Only
5	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per Drawing & Technical Specification. Complete as per Specifications.	m	80.00	135.00	Rupees One Hundred Thirty Five Only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	323.10	80.00	Rupees Eighty Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,